Next Page

Performance Inspection Procedures

The Performance Inspection Procedures (PIP) are a set of manual test procedures used for an operational closed-case evaluation of the LIFEPAK 20 defibrillator/monitor series. This section describes the test procedures you will perform to determine if the LIFEPAK 20 defibrillator/monitor series is operating within the required specifications. Investigate and correct any malfunctions or out-of-tolerance conditions detected during the PIP.

The PIP comprises safety and performance tests recommended by AHA/ASHE (American Hospital Association/American Society for Hospital Engineering) *Maintenance Management for Medical Equipment* and International Electrotechnical Commission (IEC) Technical Report 1288-2, *Maintenance of Cardiac Defibrillators-Monitors*.

Perform the PIP as part of a regularly scheduled preventive maintenance routine. Also, perform the PIP after any repair, replacement, or calibration procedure. Print the PIP Checklist to record the test results. Also refer to the **Operator Checklist** for additional items.

- **PIP Scope and Applicability**
- **PIP Resource Requirements**
- **PIP Test Equipment Requirements**
- **PIP Instructions**
- **PIP Summary of Leakage Current Specifications**

Back

Index

PIP – Checklist

3201896_R_PIP-TCP.pdf Page 1 of 69

PIP – Scope and Applicability

The PIP applies to the LIFEPAK 20 Defibrillator/Monitor series exclusively. To complete the PIP, you must perform the combination of manual tests outlined in the PIP – Instructions section of this electronic service manual. All PIP tests applicable to the LIFEPAK 20 Defibrillator/Monitor series configuration under test must be performed.

Refer to the **PIP** – **Resource Requirements** for a listing of the necessary qualifications for PIP equipment, test equipment verification, workstation power, and personnel.

Refer to the **PIP – Test Equipment Requirements** for a listing of test equipment, including specifications, required to complete the PIP.

The **PIP – Checklist** is provided as an optional tool for recording test results.

3201896_R_PIP-TCP.pdf Page 2 of 69





PIP – Resource Requirements

	This section describes the requirements for PIP equipment, PIP test equipment verification, PIP workstation power, and PIP personnel.
PIP – Equipment	To perform the PIP, you must use the equipment listed in the PIP-Test Equipment Requirements table. Although the table lists specific test equipment by manufacturer, test equipment with equivalent specifications may be substituted.
PIP – Test Equipment Verification	All test equipment used to perform the PIP must have a current calibration label, issued by a certified calibration facility.
PIP – Workstation Power	The ac line power to the workstation used must be connected to a grounded power source.
PIP – Personnel	Service personnel who perform the PIP must be properly qualified and thoroughly familiar with the operation of the LIFEPAK 20 defibrillator/monitor series, meeting the requirements described in Service Personnel Qualifications.

3201896_R_PIP-TCP.pdf Page 3 of 69

nts



Next Page 🕨

PIP – Test Equipment Requirements

The following is a list of test equipment required to conduct the PIP.

Equipment	Specifications	Manufacturer	
Patient Simulator	Simultaneous 12-lead output Rates: 30 bpm, 120 bpm @ 1 mv Rate accuracy: <u>+</u> 1%	Fluke Biomedical Corp. 215A/217A or equivalent	
Defibrillator Analyzer ^a	Energy range: 0 to 450 J Load resistance: 50 z ±1% Accuracy: ±2% +2 J Waveforms: NSR, VF, and Sine Wave	BIO-TEK [®] QED-6 [™] , with test posts accessory (Software Version 2.07, or greater) or equivalent	
Safety Analyzer	110 or 220 Vac line voltage Current range: 0-1999 pA Current accuracy: 5% of reading or 1 digit (whichever is greater)	Dale Model 600 (120 vac line input) or 600E (240 vac line input) or equivalent	
Remote Sync Test Pulse Generator	A pulse train 5Vp-p (0-5V) , 5 to 200mS wide, 120 PPM (2Hz)	Physio-Control PN 3205653 or equivalent	

a. Some energy meters are not accurate for biphasic waveforms; contact your defibrillator analyzer's manufacturer for more information.

▲ Table of Contents ▲ Section Contents

3201896_R_PIP-TCP.pdf Page 4 of 69

Back

Index

Next Page

PIP – Test Equipment Requirements

Equipment Specifications		Manufacturer	
Decade Resistance Box	0 to 9 Mz resistance box Resolution: 1 z; Accuracy: ±1%	IET RS-200 Resistance Substituter or equivalent	
Fixture Assembly, Impedance box to electrode adapter		Physio-Control PN 3205651	
Analog ECG Output Cable (optional)	Connects to the DB-15 connector	Physio-Control PN 3202553	
DB15 Cable	Connects to the DB-15 connector		
QUIK-COMBO test post adapter	Connects to QUIK-COMBO Therapy Cable	Physio-Control PN 3005302	
3-Lead ECG cable		Physio-Control PN 3006218-02	
5-Lead ECG cable		Physio-Control PN 3200496	
General purpose oscilloscope (optional)	Bandwidth: dc to 2 MHz Vertical accuracy: <u>+</u> 3% (5 mV – 5 v/div.) Horizontal Time Base Accuracy: <u>+</u> 5%	Tektronix [®] 2232 or equivalent	

3201896_R_PIP-TCP.pdf Page 5 of 69

▲ Table of Contents ▲ Section Contents



Index 🕨

Next Page 🕨

Index 🕨

Next Page 🕨

PIP – Test Equipment Requirements

Equipment	Specifications	Manufacturer
Cable -Therapy, Quik- Combo, Short		Physio-Control PN 3006570
Accessory - Test Plug, QUIK-COMBO		Physio-Control PN 3201673
Standard Paddles (optional)		Physio-Control PN 3200585-00
Chassis Leakage Cable		Dale Model 600/100-2.4 m (8 ft)
LIFEPAK 20 SpO2 Leakage Cable		Physio-Control PN 3201832-004, -005, -006

3201896_R_PIP-TCP.pdf Page 6 of 69



PIP -	- General
Instru	uctions

PIP – Exterior Physical Inspection

This section lists the general instructions for performing the Performance Inspection Procedure (PIP).

- All required PIP tests applicable to the LIFEPAK 20 defibrillator/monitor configuration under test must be performed.
- The **PIP Checklist** is provided as an optional tool for the recording of test results.
- Refer to **Troubleshooting** to correct failures, then repeat the PIP.

To perform an exterior physical inspection:

- **Note:** Throughout the body of this PIP, the LIFEPAK 20 defibrillator/monitor is referred to as the Unit Under Test or UUT.
- 1. Inspect the UUT exterior for the following:
 - Damage

▲ Table of Contents ▲ Section Contents

- Excessive wear
- Improper mechanical function
- Damaged connectors
- 2. Pick up and turn over the UUT and listen for loose or rattling hardware. Locate any loose or rattling hardware and tighten or replace it.

Back

Index 🕨

Next Page

3201896_R_PIP-TCP.pdf Page 7 of 69

Previous Page

PIP – Exterior Physical Inspection (Continued)

- 3. Inspect the rubber feet on the underside of the lower enclosure. Reinstall or replace rubber feet as necessary.
- 4. Inspect the Therapy, ECG, SpO2 (if equipped), DB-9, DB-15, AED door, and IrDA connectors for damage, cracks, or contamination.
- 5. Inspect the keypads and overlays for damage, cracks, or separations.
- 6. Check all accessory cables, paddles, SpO2 sensors, and related items for expiration dates, general condition, and suitability for use.
- 7. Inspect carrying strap and mounts (if the UUT is equipped with them).
- 8. Record the results on the **PIP Checklist Inspection**.

Cleaning Paddles

To clean the paddle connection:

- 1. Disconnect the adult paddle plate from the paddle assembly.
- 2. Clean the spring contact of the adult paddle with alcohol.
- 3. Clean the pediatric electrode surface with alcohol.
- 4. Reattach the adult paddle plate to the paddle assembly.

3201896_R_PIP-TCP.pdf Page 8 of 69

ents



PIP-Setup

Previous Page

WARNING!

▲ Table of Contents ▲ Section Contents

Shock hazard. The UUT discharges up to 360 J of electrical energy through the defibrillator cable. You must safely discharge this electrical energy as described in this PIP. Do not attempt to perform this procedure unless you are thoroughly familiar with the operation of the UUT.

Back

Index

Next Page

To set up the UUT in preparation for the PIP:

- 1. Install a roll of paper into the printer.
- 2. Connect the ac power cord into the UUT.

3201896_R_PIP-TCP.pdf Page 9 of 69

PIP- Power On/ Self-Test



To perform the PIP Power On/Self-Test:

- 1. Press the ON button to initiate the UUT nominal five-second power-on self-test routine.
- **Note:** The initial display includes Physio-Control Logo and LIFEPAK 20 defibrillator/monitor series, and the self test in progress, as shown to the upper left.
- 2. Verify that the UUT completes the Power On sequence.
- 3. Verify the AC Main indicator is ON.
- 4. Verify that the Service indicator is off.
- 5. Record the results in the PIP Checklist
- 6. Turn the UUT off.

3201896_R_PIP-TCP.pdf Page 10 of 69



8pC2

nts 🗸





PIP- Date and Time

Clock / Date/Time				
Changes will take effect next time unit is turned on				
Date	2002 / JUL / 18			
Time	08 : 30	24 hr		
	Previo	us Page		

To test the UUT date and time:

- 1. Turn the UUT ON.
- 2. Press Options key.
- 3. Select **Date/Time**...from the Options menu.
- 4. Verify that the correct date and time values are displayed on the LCD.

Note: If the date and time are incorrect, set date and time as needed.

- 5. Record the results on the PIP Checklist
- 6. Turn the UUT off.

3201896_R_PIP-TCP.pdf Page 11 of 69

Table of Contents





Next Page 🕨

PIP- ECG Leads Characteristics setup

The ECG Lead Characteristics, set up the Patient Simulator, UUT as shown below. Continue to the PIP – ECG Lead Characteristics Procedure on the next page when you complete the setup.



Back

Index

Next Page

3201896_R_PIP-TCP.pdf Page 12 of 69

▲ Table of Contents ▲ Section Contents

Previous Page

PIP- ECG Lea	ds To	test ECG Leads Characteristics:
Characteristics	5 1.	Establish the PIP – ECG Lead Characteristics setup shown in the figure on the previous page.
	2.	Program the patient simulator output for a 60 BPM, NSR.
	3.	Turn the UUT on.
	4.	Set the UUT lead selection to LEAD II.
	5.	Remove the LL lead from the patient simulator.
	6.	Verify the UUT displays an LL LEADS OFF screen message.
	7.	Reconnect the LL lead.
	8.	Remove the RA lead from the patient simulator.
	9.	Verify the UUT displays an RA LEADS OFF screen message.
	10	. Reconnect the RA lead.
	11.	. Set the UUT lead selection to LEAD I.
	12	. Remove the LA lead from the patient simulator.
		. Verify the UUT displays an LA LEADS OFF screen message.
	14	. Reconnect the LA lead. 3201896_R_PIP-TCP.pdf Page 13 of 69
Previous Page	▲ Table of Conte	ents ◀◀ Section Contents 🔁 Back Index ▶▶ Next Page I

Next Page 🕨





Lead	Printed Peak-to-Peak		
	18 mm to 22 mm		
	36 mm to 44 mm		
С	36 mm to 44 mm		

- 15. For 5 Lead ECG only: Set the UUT lead selection to LEAD II.
- 16. Remove the RL lead from the patient simulator.
- 17. Verify the UUT displays an ECG LEADS OFF screen message.
- 18. For 5 Lead ECG only: Set the UUT lead selection to LEAD C.
- 19. Remove the V1(C) lead from the patient simulator.
- 20. Verify the UUT displays a C LEADS OFF screen message.
- 21. Reconnect the V1(C) lead.
- 22. Program the patient simulator output for a 1 mV, 10 Hz sine wave.
- 23. Set the ECG size to 4.0 and lead selection to LEAD II.
- 24. Record five seconds of ECG Lead II and confirm the printed signal amplitude is 36 mm to 44 mm peak-to-peak.
- 25. Repeat Steps 23 and 24 for Lead I, substituting the signal amplitudes give in the table at the left.
- 26. For 5 Lead ECG only: Repeat Steps 23 and 24 for Lead C, substituting the signal amplitudes give in the table at the left.

Back

Index

Next Page

- 27. Record the results on the **PIP Checklist**
- 28. Remove the ECG cable and turn the UUT off.

3201896_R_PIP-TCP.pdf Page 14 of 69

Previous Page

PIP- Printer test

Service / Test / Printer				
Start	printer test			
Start Previous Page				

To test the 50 mm printer:

- 1. Hold down OPTIONS and EVENT controls and turn on the device. Hold the controls until Enter Passcode appears. Enter passcode 5433.
- 2. Select SERVICE from the Setup menu. Enter passcode 5433.
- 3. Select PRINTER from the on-screen Service/Test menu.
- 4. Select START from the Service/Test/Printer screen to print a test strip.
- 5. Inspect the test strip for the following attributes:
 - The large "X" form is printed without missing dots.
 - Four horizontal lines (one very close to the lower paper margin).
 - The character set is printed clearly without broken characters.
 - Vertical lines spaced 25 mm <u>+</u>5% apart.
- 6. Open the printer door and verify the CHECK PRINTER message appears at the bottom of the screen.

Back

Index

Next Page

- 7. Close the printer door.
- 8. Press the HOME key to return to Service menu. Turn the UUT off.
- 9. Record the results on the PIP Checklist

3201896_R_PIP-TCP.pdf Page 15 of 69

ntents

PIP- Oximeter test



To test the SpO2 Oximeter:

Note: Complete only if the UUT is equipped with the SpO2 Oximeter option.

- 1. Connect the Oximeter finger probe to the SpO2 connector as shown at the left.
- 2. Verify the SpO2 parameter region appears on the display.
- 3. Place your index finger into the SpO2 probe. Allow several seconds for the probe to find your pulse.

Back

- 4. Confirm the SpO2 reading is between 90% and 100%.
- 5. Disconnect the SpO2 probe.
- 6. Record the results on the PIP Checklist
- 7. Turn the UUT off.

▲ Table of Contents ▲ Section Contents

3201896_R_PIP-TCP.pdf Page 16 of 69

Index



Next Page

PIP – Instructions

PIP- Therapy-Impedance Sense setup

To perform the Therapy Impedance Sense test, set up the Resistance box and UUT as shown below. Continue to the PIP – Therapy Impedance Sense Procedure on the next page when you complete the setup.



Previous Page

PIP- Therapy-Impedance Sense

To test Therapy Impedance Sense:

- 1. Establish the PIP Therapy Impedance Sense setup shown in the figure on the previous page.
- 2. Set the decade resistance box to 50Z.
- 3. Turn on the UUT.
- 4. Set the UUT: manual mode, ECG Size to 1.0, lead selection to PADDLES.
- 5. Set the decade resistance box to 248 z.
- 6. Verify the UUT display displays the PADDLES LEADS OFF message.
- 7. Set the decade resistance box to 182 z.
- 8. Verify the PADDLES LEADS OFF message is removed from the UUT display.
- 9. Record the results on the PIP Checklist
- 10. Turn the UUT off.
- 11. Remove the decade resistance box.

3201896_R_PIP-TCP.pdf Page 18 of 69

▲ Table of Contents ▲ Section Contents

ts



Index

Next Page

PIP- Therapy User Test

To test the Therapy User test:

1. If the unit is equipped with Quik- combo cable: Connect the Therapy cable between the UUT and the QUIK-COMBO test plug.

If the unit is equipped with Standard Paddles: Install standard paddles into the UUT and place the UUT's paddles in the paddle wells.

Note: Verify that the metal surfaces of the standard paddles and paddle test contacts in the device paddle wells are free of burn and arc marks. Also check that these surfaces are free of pits, scratches, insulating films, contaminants or raised nicks that can be felt with the finger tip. Check therapy connector for pin damage.

- 2. Set the UUT lead selection to PADDLES.
- 3. Press the OPTIONS button and select USER TEST from the Options screen.
- 4. Select YES from the Options/Users Test screen.
- 5. Push Speed Dial to initiate the self test and the user test. The self test and the user test are performed. The User Test Succeeded report is printed when test is complete.

Back

Index

Next Page

6. Record the results on the **PIP Checklist**.

The unit automatically turns off after successfully completing the test. 3201896_R_PIP-TCP.pdf Page 19 of 69

Previous Page Table of Contents Section Contents

PIP- Therapy-Delivered Energy and Sync setup

To perform the Therapy – Delivered Energy and Synchoronous cardioversion test, set up the defibrillator analyzer and UUT as shown on the next page. Continue to the PIP – Therapy Delivered Energy and Synchoronous cardioversion Procedure on the following page when you complete the setup.

- **Note:** Ensure proper test connections to the Defibrillator Analyzer. To avoid damage to the Analyzer or defibrillator;
- 1. Do NOT apply defibrillator pulses to the pacer inputs of the analyzer (if the analyzer is equipped with pacer inputs
- 2. If testing with standard paddles, verify that the metal surfaces of the paddlesare free of burn or arc marks and are free of pits, scratches, insulating films, contaminants or raised nicks that can be felt with the finger tips.

3201896_R_PIP-TCP.pdf Page 20 of 69



PIP - Therapy -Delivered Energy and Sync Setup (Continued)



Index

Next Page

3201896_R_PIP-TCP.pdf Page 21 of 69

Back

PIP- Therapy-Delivered Energy and Sync

To test Therapy – delivered energy and Synchoronous cardioversion:

- Establish the PIP Therapy Delivered Energy and Synchoronous 1. cardioversion setup shown in the figure on the previous page.
- Turn on the UUT. 2
- Set the UUT: manual mode, ECG Size to 1.0, lead selection to PADDLES. 3.
- Set the defibrillator analyzer to measure SYNC. 4.
- 5. Press the SYNC button ON and select LOCAL, if Remote Sync is set to on.
- Verify the SYNC LED turns on and R-wave markers appear on the ECG 6. waveform.
- Press the ENERGY SELECT button to select 2 J. 7.
- 8. Press the CHARGE button and wait for the UUT to reach full charge. Then press the SHOCK button to discharge the UUT.

Note: For standard paddles use the APEX PADDLE CHARGE button on the paddles.

Back

Index

Next Page

- Verify the defibrillator analyzer measures a sync R-wave of 60 ms or less. 9.
- 10. Set the defibrillator analyzer to measure **ENRG** (press ESC, then ENRG).

3201896_R_PIP-TCP.pdf Page 22 of 69

Previous Page

PIP- Therapy-Delivered Energy and Sync (Continued)

- 11. Repeat Steps 7 and 8 for the all energy levels specified in the table.
- 12. Verify the defibrillator analyzer indicates the delivered energy is within the acceptable output limits, shown below.

Energy Level (J) Acceptable Output (J)	
2	1.0 to 3.0
70	65.1 to 74.9
360	334.8 to 385.2

- **Note:** Perform the **TCP Defibrillator Calibration** if the delivered energy falls outside of the acceptable output range.
- 13. Press the Code Summary key. Verify that the Code Summary key is working properly.
- 14. Press Alarm key. Verify that the Alarm menu are displayed on the LCD.
- 15. Record the results on the PIP Checklist
- 16. Turn the UUT off.

3201896_R_PIP-TCP.pdf Page 23 of 69

ts



Index

Next Page

PIP – Instructions

PIP- Therapy -Paddles ECG Gain and AED mode test

To test Therapy Paddles ECG gain and AED mode test :

- 1. To test Therapy Paddles ECG gain: Program the defibrillator analyzer output for a 1 mV, 10 Hz sine wave.
- 2. Set the UUT ECG Size to 4.0 and Lead selection to PADDLES.
- 3. Record 10 seconds of Paddles ECG and confirm the printed signal amplitude is 36 mm to 44 mm peak-to-peak.
- **Note:** The BIO-TEK QED-6 produces a 1.1 mV output; confirm the printed signal amplitude is 38 mm to 50 mm peak-to-peak.
- 4. To test AED mode test : If the unit is equipped with standard paddles, remove standard paddles out of the UUT's therapy connector and connect the Therapy Quik-combo cable between the UUT and the Defib analyzer.
- 5. Press the ANALYZER key to turn the AED mode on. Verify that the AED mode on.
- 6. Verify that the voice prompts are clearly audible:

•ANALYZING NOW, STAND CLEAR.

- 7. Press the ENERGY key. Verify that the UUT switches to Manual mode.
- 8. Record the results on the PIP Checklist 3201896_R_PIP-TCP.pdf Page 24 of 69

Previous Page **I** Table of Contents **I** Section Contents

Back

PIP- Therapy- Remote Sync Test Setup

Previous Page

To perform the Therapy- Remote Sync test, set up the Defibrillator Analyzer, Remote Sync Test Pulse Generator, and UUT as shown below. Continue to the PIP – Therapy Remote Sync Test Procedure on the next page when you complete the setup.



PIP- Therapy- Remote Sync Test

- To test Therapy- Remote Sync :
- 1. Establish the PIP Therapy- Remote Sync Test setup shown in the figure on the previous page.

Note: A function generator can be used instead of a Remote Sync Test Pulse Generator. Set the function generator to provide a pulse train 5 Vp-p (0-5 V), 5 to 200 ms wide, 120 PPM (2 Hz).

- 2. Turn on the Remote Sync Test Pulse Generator.
- 3. On the Manual Mode Setup page, set the UUT to Remote Sync ON.
- 4. Turn the UUT off , then turn the UUT on.
- 5. Set the UUT: manual mode, lead selection to PADDLES.
- 6. Press the SYNC button on the UUT.
- 7. On the Sync Mode screen, select REMOTE.
- 8. Verify the SYNC LED is flashing.
- 9. Charge the UUT to 200 J.
- 10. Upon reaching full charge, press the SHOCK button to discharge the UUT.

Back

Index

Next Page

3201896_R_PIP-TCP.pdf Page 26 of 69

ntents

PIP-Therapy- Remote Sync Test (Continued)

- 11. Verify the UUT displays "ENERGY DELIVERED" screen message (for SW-20 version or below) or switches out of remote sync mode (for SW-26 version or above).
- 12. Record the results on the PIP Checklist. Turn the UUT off.

3201896_R_PIP-TCP.pdf Page 27 of 69







Next Page

PIP – Instructions

PIP- Pacer Option Characteristics set up

To perform the Pacer Option Characteristics test, set up the Defibrillator 1. Analyzer and UUT as shown below. Continue to the PIP – Pacer Option Characteristics Procedure on the next page when you complete the setup.



Previous Page

PIP- Pacer Option Characteristics

To test Pacer Option Characteristics:

Note: Skip this test if using a nonpacing defibrillator.

- 1. Establish the PIP Pacer Option Characteristics setup shown in the figure on the previous page.
- 2. Set the defibrillator analyzer to measure peak current pacing parameters.
- 3. Press the PACER control on the UUT.
- 4. Verify the PACER control LED lights and the PACER overlay appears.
- 5. Disconnect one of the Test Post Adapter snaps from the defibrillator analyzer.
- 6. Verify the PACING STOPPED/CONNECT ELECTRODES overlay appears accompanied by an audible alarm.
- 7. Reconnect the Test Post Adapter snap.
- 8. Verify the overlay CONNECT ELECTRODES disappears and the alarm stops.
- 9. Set the defibrillator analyzer to output PACE, MEAS.
- 10. Press all the keys on Pacer panel, verify that all keys are working properly.

3201896_R_PIP-TCP.pdf Page 29 of 69

ntents



Index

PIP- Pacer Option Characteristics (Continued).

- 11. At 40 PPM Rate, press the UUT CURRENT button to select a pacer current of 10 mA.
- 12. Verify the defibrillator analyzer indicates the pacer output current is within the acceptable output limits, shown below:

Peak Current Level (mA)	Acceptable Output (mA)
10	5 to 15
100	95 to 105
200	190 to 210

- 13. Repeat step 10 and 11 for the remaining peak pacer currents specified in the table.
- 14. At 40 PPM Rate and 200 mA, verify the defibrillator analyzer indicates the pacer pulse width is between 19.0 and 21.0 ms.
- 15. Press the UUT PACER control to terminate pacing.
- 16. Record the results on the PIP Checklist
- 17. Turn the UUT off.

3201896_R_PIP-TCP.pdf Page 30 of 69

its



PIP- Leakage Current

Note: Each test result applies to a safety analyzer operating from a 120 vac source or 240 vac source, unless indicated otherwise. For exceptions, the test result includes the safety analyzer operating source. For example, 300 µA (120 vac) or 500 µA (240 vac). All test results are summarized in the Leakage Current Specifications Summary Table.

WARNING!

Shock Hazard. Failure to properly perform these tests could result in a failure to detect excessive leakage current. Make sure you are familiar with your test equipment and these test performance procedures.

3201896_R_PIP-TCP.pdf Page 31 of 69

▲ Table of Contents ▲ Section Contents

Back





PIP- Leakage Current

Check the leakage current in accordance with the following industry standards:

- AAMI/ANSI (Association for the Advancement of Medical Instrumentation/ ٠ American National Standards Institute) DF2-1989, DF39-1993
- IEC (International Electrotechnical Commission) 601-1 and 601-2-4 . Earth Ground: Third wire ground.

Normal Condition (N.C.): AC voltage is applied in either normal or reversed polarity i.e. measurements made with the POLARITY switch in both NORMAL and REVERSED positions. The earth ground is intact during these measurements (if LIFT GND switch is not pressed).

Single Fault Condition (S.F.C.): AC voltage is applied in either normal or reversed polarity i.e. measurements made with the POLARITY switch in both NORMAL and REVERSED positions. The earth ground is **NOT** intact during these measurements (if LIFT GND switch is pressed).

Note: Due to the variety of safety analyzers that may be used for these tests, this service manual provides only general instructions. For information about configuration and testing methods, refer to your safety analyzer operating instructions.

3201896_R_PIP-TCP.pdf Page 32 of 69

Table of Contents < Section Contents</p>



Index

Next Page

PIP- Ground Resistance Test Setup

Previous Page

To test the Ground Resistance Test, set up the safety analyzer and UUT as shown below. Continue to the PIP – Ground Resistance Test Procedure on the next page when you complete the setup.



Back

Index 🕨

Next Page

3201896_R_PIP-TCP.pdf Page 33 of 69

Next Page

PIP – Instructions

PIP- Ground Resistance Test

Previous Page

To test Ground Resistance Test:

- 1. Establish the PIP Ground Resistance Test Setup as shown in the figure on the previous page. **The UUT is off for this test.**
- 2. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Any	Center	Ohms	Resistance	Any

Back

Index

- 3. Verify measured ground resistance test is less than 0.5 ohms.
- 4. Record the results in the PIP Checklist

3201896_R_PIP-TCP.pdf Page 34 of 69

PIP- Chassis Leakage Current Setup

Previous Page

To test chassis leakage current, set up the safety analyzer and LIFEPAK 20 defibrillator/monitor (UUT) as shown below. Continue to the PIP – Chassis Leakage Current Procedure when you complete the setup.



Back

Index 🕨

Next Page

3201896_R_PIP-TCP.pdf Page 35 of 69

PIP- Chassis Leakage Current test

To test Chassis Leakage Current:

- 1. Establish the PIP Chassis Leakage Current Setup as shown in the figure on the previous page.
- 2. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Closed	Normal/Reversed	Leakage µA	Chassis	All

- **Note:** When operating the Polarity Switch, be sure to pause in the Off (middle) position when switching between Normal and Reversed Polarities.
- 3. Connect the analyzer clip to the Ground stud and turn the UUT on.
- 4. Verify measured current is less than 90 µA.
- 5. Press the LIFT GND button on the safety analyzer.
- 6. Verify measured current is less than 270 μA (120 VAC) or less than 450 μA (240 VAC).

Back

Index

Next Page

- 7. Release the LIFT GND button on the safety analyzer.
- 8. Record all results on the PIP Checklist

3201896_R_PIP-TCP.pdf Page 36 of 69

ents 🔶

PIP- Earth Leakage Current Setup

Previous Page

To test earth leakage current, set up the safety analyzer and UUT as shown below. Continue to the PIP – Earth Leakage Current Procedure when you complete the setup.



Back

Index

Next Page

3201896_R_PIP-TCP.pdf Page 37 of 69

PIP- Earth Leakage Current test

To test Earth Leakage Current:

- 1. Establish the PIP Earth Leakage Current Setup shown in the figure on the previous page.
- 2. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Closed	Normal/Reversed	Leakage µA	Earth	Any

- **Note:** When operating the Polarity Switch, be sure to pause in the Off (middle) position when switching between Normal and Reversed Polarities.
- 3. Verify measured current is less than 450 μ A.
- 4. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Open	Normal/Reversed	Leakage µA	Earth	Any

Back

Index

Next Page

- 5. Verify measured current is less than 900 μ A.
- 6. Record the results in the **PIP Checklist**.

3201896_R_PIP-TCP.pdf Page 38 of 69

▲ Table of Contents ▲ Section Contents

tents

PIP- ECG Lead Leakage Setup

Previous Page

To perform the ECG Lead Leakage Current test, set up the safety analyzer and UUT as shown below. Continue to the PIP – ECG Lead Leakage Current Procedure on the next page when you complete the setup.



PIP- ECG Lead Leakage Current test

Previous Page

To test ECG Lead Leakage Current :

- 1. Establish the PIP ECG Lead Leakage Current Setup shown in the figure on the previous page.
- 2. Turn on the UUT.
- 3. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Closed	Normal/ Reversed	Leakage µA	Lead – Gnd	ALL

- **Note:** When operating the Polarity Switch, be sure to pause in the Off (middle) position when switching between Normal and Reversed Polarities.
- 4. Verify the measured current is less than 10 μ A.
- 5. Press the LIFT GND button on the safety analyzer.
- 6. Verify the measured current is less than 50 μ A.
- 7. Release the LIFT GND button.
- 8. Set the safety analyzer controls to:

	Neutral	Polarity	Mode		Lead
	Closed	Normal/ Reversed	Leakage µA	Lead – Lead	RA
	3201896_R_PIP-	TCP.pdf Page 40 of 69			·
Table of Conter	nts I Section	Contents	Back	Index >>	Next Page

PIP- ECG Lead Leakage Current test (Continued)

9. Repeat steps 4 through 7 for the remaining (RA and LL).

10. For 5-Lead ECG: Repeat steps 4 through 7 for the remaining (RL and C)

11. Turn the UUT off.

12. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Closed	Normal	Leakage µA	Lead Iso	All

WARNING!

Shock hazard. During sink leakage tests high voltage is present on the safety analyzer electrode snaps. Do not touch the analyzer snaps or UUT connections during these tests.

13. Momentarily press the ISO TEST button on the analyzer and observe the current reading.

Back

- 14. Release the ISO TEST button.
- 15. Verify the measured current is less than 45 $\mu A.$
- 16. Record all results on the **PIP Checklist**.

3201896_R_PIP-TCP.pdf Page 41 of 69

its



PIP- SpO2 Leakage Current Setup

Previous Page

Note: Complete the following only for UUTs equipped with the SpO2 option.

The SpO2 Leakage Current, set up the safety analyzer, UUT as shown below. Continue to the PIP – SpO2 Leakage Current Procedure when you complete the setup.



PIP- SpO2 Leakage Current

To test SpO2 Leakage Current:

- 1. Establish the PIP SpO2 Leakage Current Setup shown in the figure on the previous page.
- 2. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Closed	Normal	Leakage µA	Lead Iso	С

WARNING!

Shock hazard. During sink leakage tests high voltage is present on the safety analyzer electrode snaps. Do not touch the analyzer snaps or UUT connections during these tests.

3. Momentarily press the ISO TEST button on the safety analyzer and observe the measured current reading.

Back

- 4. Release the ISO TEST button.
- 5. Verify the measured current is less than 90 μA (120 vac) or 450 μA (240 vac).
- 6. Record the results on the **PIP Checklist**.

3201896_R_PIP-TCP.pdf Page 43 of 69

ents



Next Page

Index

Next Page

PIP – Instructions

PIP- Therapy Leakage Current Setup

To perform the Therapy leakage current test, set up the safety analyzer and UUT as shown below. Continue to the PIP – Therapy Leakage Current Procedure on the next page when you complete the setup.



3201896_R_PIP-TCP.pdf Page 44 of 69

Back

PIP- Therapy Leakage Current test

To test Therapy Leakage Current :

Establish the PIP – Therapy Leakage Current Setup shown in the figure on the previous page.

1. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Closed	Normal/Reversed	Leakage µA	Lead – GND	ALL

Note: When operating the Polarity Switch, be sure to pause in the Off (middle) position when switching between Normal and Reversed Polarities.

- 2. Verify the measured current is less than $10 \mu A$.
- 3. Press the LIFT GND button on the safety analyzer.
- 4. Verify the measured current is less than 50 μ A.
- 5. Release the LIFT GND button.

▲ Table of Contents ▲ Section Contents

6. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Closed	Normal/Reversed	Leakage µA	Lead – Lead	RL or C

Back

Index

Next Page

3201896_R_PIP-TCP.pdf Page 45 of 69

Previous Page

PIP- Therapy Leakage Current test (Continued)

Note: When operating the Polarity Switch, be sure to pause in the Off (middle) position when switching between Normal and Reversed Polarities.

- 7. Repeat steps 2 through 5.
- 8. Turn the UUT off.
- 9. Set the safety analyzer controls to:

Neutral	Polarity	Mode		Lead
Closed	Normal	Leakage µA	Lead Iso	All

WARNING!

Shock hazard. During sink leakage tests high voltage is present on the safety analyzer electrode snaps. Do not touch the analyzer snaps or UUT connections during these tests.

10. Momentarily press the ISO TEST button on the safety analyzer and observe the measured current reading.

Back

Index

Next Page

- 11. Release the ISO TEST button.
- 12. Verify the measured current is less than 90 μA (120 vac) or 450 μA (240 vac).
- 13. Record the results on the **PIP Checklist**.

3201896_R_PIP-TCP.pdf Page 46 of 69

Previous Page **I** Table of Contents **I** Section Contents

itents

PIP- Record Operating Data (optional test)

Service / St	atus / Coun	ters
Go back to	o previous page	
Total Shocks		7445
360J	707	2325
225 - 325J	1215	3399
100 - 200J	466	1721
0 - 70J	23	121
Clear All	Prev	vious Page
Go back to	nrevious nane	
10 May 2001 Fault Messages Power Cycle Count Pacing Count Shock Count Power On Time Printer On Time Sp02 Operating Time	promous pago	12:58:36 Yes 385 90 1478 221.5 25.4 67.1
	Prev	vious Page

To record the operating data:

- Hold down OPTIONS and EVENT controls and turn on the device. Hold the 1 controls until Enter Passcode appears. Enter passcode 5433.
- Select SERVICE from the Setup menu. Enter passcode 5433. 2.
- Navigate to the Service/Status/Counters screen. On the PIP Checklist 3. record the shocks since last reset (in boxes) and total shocks since the device was built. Select CLEAR ALL to reset box counters (if desired).

Back

Index

Next Page

- Select PREVIOUS PAGE. 4.
- Select DEVICE LOG. record the following on the **PIP Checklist**: 5.
 - Power Cycle Count
 - Pacing Count
 - Shock Count
 - Power On Time
 - Printer On Time
 - SpO2 Operating Time
- Turn the UUT off. 6

3201896_R_PIP-TCP.pdf Page 47 of 69

Previous Page

PIP- Contrast Test — LCD (optional test)



To test screen contrast:

- 1. Hold down OPTIONS and EVENT controls and turn on the device. Hold the controls until Enter Passcode appears. Enter passcode 5433.
- 2. Select SERVICE from the Setup menu. Enter passcode 5433.
- 3. Enter the Service/Tests screen and select Contrast. The LCD changes to display a square block in the center of the screen, as shown in the figure on the left.
- 4. For passive LCD only: rotate the Speed Dial. The background changes from white to black. After five seconds the PUSH SPEED DIAL TO EXIT message appears on the screen.
- 5. Press the Speed Dial to exit the test.
- **Note:** If you accidentally select a pure white or pure black background when exiting the contrast test, press the CONTRAST button (), rotate the Speed Dial to the desired display, and press the Speed Dial.

Back

Index

Next Page

- 6. Record the results in the PIP Checklist
- 7. Turn the UUT off.

3201896_R_PIP-TCP.pdf Page 48 of 69



ents

PIP- Pixels test (optional test)

Potate Sneed Dial to test nivels

To test the display pixels:

- 1. Hold down OPTIONS and EVENT controls and turn on the device. Hold the controls until Enter Passcode appears. Enter passcode 5433.
- 2. Select **SERVICE** from the Setup menu. Enter passcode 5433.
- 3. Enter the Service/Tests screen and select pixels. The pixels test screen appears, as shown in the figure on the left.
- 4. Carefully examine the screen for any anomalies. After five seconds, the ROTATE SPEED DIAL TO TEST PIXELS message appears on the screen.
- 5. Press the Speed Dial to exit the test.
- 6. Record the results in the **PIP Checklist**.
- 7. Turn the UUT off.

3201896_R_PIP-TCP.pdf Page 49 of 69

Table of Contents





Next Page

PIP- Keypad test (optional test)

P	ress Flas	ning Butt	ton		
				nergy Select	
				Charge *	
Door	Ana	lyze	Shock *		
Print	Lead	Size	Sync *		
Code Summary				Pacer *	
Event	1		V	Rate	
Contrast	Alarms V Current		Current	-	
Home	Options			Pause	
Pi	ish Sneed	Dial to	evit	1 8 8 3 6	

* The button is not available on nonpacing models. Press the keypad in the button's location to verify the button.

To test the keypad:

- Hold down OPTIONS and EVENT controls and turn on the device. Hold the 1 controls until Enter Passcode appears. Enter passcode 5433.
- 2. Select SERVICE from the Setup menu. Enter passcode 5433.
- Select TESTS... from the on-screen Service menu. Navigate to the Service/ 3. Tests/Buttons screen.
- 4. Press each front panel control when prompted by the flashing control legend (although you may press the controls in any order).
- 5. Verify with each control pressed that its associated text box is highlighted. All buttons must be tested regardless of defibrillator configuration.
- **Note:** Door button is hidden in the elastomer keypad and it is located between the OPTION and PAUSE buttons.
- **Note:** A failure is indicated by a control text box that is not highlighted. It is normal for the controls with up/down arrows to highlight only the arrows.

Back

Index

Next Page

- Verify the key check sound indicating that the button is working. 6.
- Press the Speed Dial at the end of the test. 7.
- Record the results on the **PIP Checklist**. 8.

3201896_R_PIP-TCP.pdf Page 50 of 69

Previous Page

PIP- Audio test (optional test)

Service / T	est / Voice/Tone
Analyzing n	owStand Clear
Start v	oice/tone test
Start	Previous Page

To test the UUT voice prompts and tones:

- 1. Hold down OPTIONS and EVENT controls and turn on the device. Hold the controls until Enter Passcode appears. Enter passcode 5433.
- 2. Select **SERVICE** from the Setup menu. Enter passcode 5433.
- 3. Select VOICE/TONE... from the Service/Tests sub-menu.
- 4. Select START. Voice prompts sound in the speaker.
- 5. When satisfied that the voice prompts are clearly audible and reproduced without distortion, turn off the device.
- **Note:** You may listen to a complete replay of all voice prompts and tones, but it is not required for verification of this function.
- 6. Record the results on the **PIP Checklist**.
- 7. Turn the UUT off.

3201896_R_PIP-TCP.pdf Page 51 of 69

▲ Table of Contents ▲ Section Contents

Ba





PIP- ECG Analog Output (optional test)



General Purpose Oscilloscope

To test the ECG analog output:

Note: This test is optional. Perform only if this feature is used.

- 1. Establish the test setup as shown at the left.
- 2. Using the ECG cable supplied with the UUT, input a 1 mV 10 Hz sine wave from the patient simulator.
- 3. Set the UUT lead selection to LEAD II. (The ECG analog output is in real time at a nominal 1 v/mV and is not affected by the device ECG size setting.)
- 4. Verify the amplitude of the signal displayed on the oscilloscope is between 0.85 Vp-p and 1.15 Vp-p.
- 5. Disconnect the Analog ECG Output Cable from the UUT and oscilloscope.

Back

Index

Next Page

- 6. Record the results on the **PIP Checklist**.
- 7. Turn the UUT off.

▲ Table of Contents ▲ Section Contents

3201896_R_PIP-TCP.pdf Page 52 of 69

PIP – Summary of Leakage Current Specifications

The following summarizes leakage current specifications. NC=Normal Condition SFC = Single Fault Condition

Leakage Test		Maximum Leakage Current Specifications		
Type of Test	Lead Test	Analyzer @ 120 vac	Analyzer @ 240 vac	
Chassis Leakage	Contact of Ground Stud	NC: 90 µA	NC: 90 µA	
		SFC: 270 µA	SFC: 450 µA	
Earth Leakage	Closed Neutral	450 µA	450 µA	
	Open Neutral	900 µA	900 µA	
3-Lead ECG Source LEAD-GND	All-GND	NC: 10 μA	NC: 10 μA	
		SFC: 50 µA	SFC: 50 µA	
3-Lead ECG Source LEAD-LEAD	RA	NC: 10 μA	NC: 10 μA	
		SFC: 50 µA	SFC: 50 µA	
	LA	NC: 10 μA	NC: 10 μA	
		SFC: 50 µA	SFC: 50 µA	
	LL	NC: 10 μA	NC: 10 µA	
		SFC: 50 µA	SFC: 50 µA	
3-Lead ECG Sink Leakage	ISO Test	45 µA	45 µA	
Drovious Dogo III Toble of Con	3201896_R_PIP-TCP.pdf Page	53 of 69		

PIP – Summary of Leakage Current Specifications

Leakage Test		Maximum Leakage Current Specifications		
Type of Test	Lead Test	Analyzer @ 120 vac	Analyzer @ 240 vac	
5-Lead ECG Source LEAD-GND	ALL	NC: 10 µA	NC: 10 µA	
		SFC: 50 µA	SFC: 50 µA	
5-Lead ECG Source LEAD-LEAD	RA	NC: 10 µA	NC: 10 µA	
		SFC: 50 µA	SFC: 50 µA	
	RL	NC: 10 µA	NC: 10 µA	
		SFC: 50 µA	SFC: 50 µA	
	LA	NC: 10 µA	NC: 10 µA	
		SFC: 50 µA	SFC: 50 µA	
	LL	NC: 10 µA	NC: 10 µA	
		SFC: 50 µA	SFC: 50 µA	
	С	NC: 10 µA	NC: 10 µA	
		SFC: 50 µA	SFC: 50 µA	
5-Lead ECG Sink Leakage	ISO Test	45 μΑ	45 µA	

3201896_R_PIP-TCP.pdf Page 54 of 69

Index

PIP – Summary of Leakage Current Specifications

Leakage Test		Maximum Leakage Cu	rrent Specifications
Type of Test	Lead Test	Analyzer @ 120 vac	Analyzer @ 240 vac
SpO2 Sink Leakage	ISO Test	90 µA	450 µA
Paddles Source LEAD-GND	AII–GND	NC: 10 µA	NC: 10 µA
		SFC: 50 µA	SFC: 50 µA
Paddles Source LEAD-LEAD	RL or C	NC: 10 µA	NC: 10 µA
		SFC: 50 µA	SFC: 50 µA
Paddles Sink Leakage	ISO Test	90 µA	450 µA
QUIK-COMBO Source LEAD-GND	AII–GND	NC: 10 µA	NC: 10 µA
		SFC: 50 µA	SFC: 50 µA
QUIK-COMBO Source LEAD- LEAD	RL or C	NC: 10 μA	NC: 10 μA
		SFC: 50 µA	SFC: 50 µA
QUIK-COMBO Sink Leakage	ISO Test	90 µA	450 µA

3201896_R_PIP-TCP.pdf Page 55 of 69





Next Page

Instrument The Instrument Calibration section contains the Test and Calibration Procedure (TCP). Perform the procedures in this section as necessary after replacement of Calibration device components or to correct out-of-specification conditions detected during the PIP. The following procedures may be performed in any order. **Note:** Anytime the device is calibrated or opened for repair or component replacement, it must successfully pass all portions of the closed-case **Performance Inspection Procedure (PIP). TCP – Scope and Applicability TCP – Resource Requirements TCP – Test Equipment Requirements** TCP – Setup **TCP – Defibrillator Calibration Menu Access TCP – Defibrillator Calibration TCP – Delivered Energy Test TCP – Defibrillator Output Waveform Test (Optional) TCP** - Defibrillator Isolation Test

3201896_R_PIP-TCP.pdf Page 56 of 69

Back

Index

TCP – Scope and Applicability

This TCP applies to the LIFEPAK 20 defibrillator/monitor exclusively. You may perform the procedures outlined in this section in any order.

Note: Prior to its return to active use, the LIFEPAK 20 defibrillator/monitor must successfully pass all portions of the closed-case Performance Inspection Procedure (PIP) anytime the device is opened for repair, component replacement, or after calibration.

Refer to **TCP** – **Resource Requirements** for necessary equipment, test equipment verification, workstation power, and qualifications of the TCP personnel.

Refer to **TCP – Test Equipment Requirements** for a listing of test equipment, including specifications, required to complete the TCP.

3201896_R_PIP-TCP.pdf Page 57 of 69

Back



TCP – Resource Requirements

	This section describes the requirements for TCP equipment, TCP test equipment verification, TCP workstation power, and TCP personnel.
TCP – Equipment	To perform the TCP, you must use the equipment listed in the TCP – Test Equipment Requirements table on the next page. Although the table lists specific test equipment by manufacturer, test equipment with equivalent specifications may be substituted.
TCP – Test Equipment Verification	All test equipment used to perform the TCP must have a current calibration label. The calibration label must be issued by a certified calibration facility.
TCP – Workstation Power	The ac power to the workstation used must be connected to a grounded power source.
TCP – Personnel	Technicians who perform the TCP must be properly qualified and thoroughly familiar with the operation of the LIFEPAK 20 defibrillator/monitor, meeting the requirements described in Service Personnel Qualifications .

3201896_R_PIP-TCP.pdf Page 58 of 69

▲ Table of Contents ▲ Section Contents



TCP – Test Equipment Requirements

You need the following test equipment, or equivalent, to conduct the TCP.

Back

Index

Next Page

Equipment	Specifications	Manufacturer
Defibrillator Analyzer ^a	Energy range: 0 to 450 J Load resistance: 50 Z ±1% Accuracy: ±2% +2 J Waveforms: NSR, VF, and Sine Wave	BIO-TEK [®] QED-6 [™] , with test posts accessory (software version 2.07, or greater) or equivalent
QUIK-COMBO test post adapter	Connects to QUIK-COMBO therapy cable	Physio-Control PN 3005302
Cable -Therapy, Quik-Combo Pretest		Physio-Control PN 3011517
Defibrillator Isolation test load	Resistor - Test Load, 200z, Silicon Coated, 50 Watt, 5%	Physio-Control PN 3205570
General purpose oscilloscope	Bandwidth: dc to 2 MHz Vertical accuracy: <u>+</u> 3% (5 mV – 5 v/div.) Horizontal Time Base Accuracy: <u>+</u> 5%	Tektronix [®] 2232 or equivalent

a. Some energy meters are not accurate for biphasic waveforms; contact your defibrillator analyzer's manufacturer for more information.

3201896_R_PIP-TCP.pdf Page 59 of 69

LIFEPAK 20 Defibrillator/Monitor Series

TCP – Setup



The following describes the LIFEPAK 20 defibrillator/monitor setup for the TCP.

WARNING!

Shock hazard. When discharged during this TCP, the device discharges up to 360 J of electrical energy through the defibrillator cable. You must safely discharge this electrical energy as described in this TCP. Do not attempt to perform this procedure unless you are thoroughly familiar with the operation of the device.

To set up the LIFEPAK 20 defibrillator/monitor for the TCP: Install a roll of paper into the printer.

- **Note:** Ensure that the LOW BATTERY screen message does not appear when the device is turned on and during defibrillator calibration by installing a fully functional battery in the UUT.
- **Note:** If the A12 Printer was replaced, save the piece of paper inside the printer that has the printhead resistance written down.
- **Note:** Do not connect anything to the therapy connector, except as directed during this procedure.

3201896_R_PIP-TCP.pdf Page 60 of 69



ents



Index

Next Page

TCP – Defibrillator Calibration Menu Access

Ser	vice
Perform defibril Defib Cal Tests Status	lator calibration Set Passcode Maint Prompt Setup

To enter the Service screen:

- 1. Complete the TCP Setup.
- 2. Place the UUT in service mode.
- 3. Select DEFIB CAL.. from the Service screen. The Service/Calibration screen appears.

3201896_R_PIP-TCP.pdf Page 61 of 69







Next Page 🕨

LIFEPAK 20 Defibrillator/Monitor Series

TCP – Defibrillator Calibration



To perform the defibrillator calibration procedure:

 Connect the UUT to the defibrillator analyzer. Make sure the QUIK-COMBO (+) terminal is connected to apex (+).

Note: Adapt this procedure to use standard paddles, if desired.

Note: Ensure proper test setup connections to the Defibrillator Analyzer. To avoid damage to the Analyzer or defibrillator, do NOT apply defibrillator pulses to the pacer inputs of the analyzer (if the analyzer is equipped with pacer inputs).

Note: If testing with standard paddles, verify that the metal surfaces of the paddles are free of burn or arc marks and are free of pits, scratches, or raised nicks that can be felt with the finger tips.

Back

Index

Next Page

- 2. Set the defibrillator analyzer to measure energy, with the appropriate scale.
- 3. Access the Defib Calibration submenu.
- 4. Select DEFIB CAL from the Service Screen.
- 5. Select START to initiate the calibration routine.
- 6. Follow the instructions on the UUT screen.

3201896_R_PIP-TCP.pdf Page 62 of 69

Previous Page

itents

TCP – Defibrillator Calibration

7. Turn off the UUT.

8. Continue directly to TCP – Delivered Energy Test on the next page.

3201896_R_PIP-TCP.pdf Page 63 of 69

Previous Page







LIFEPAK 20 Defibrillator/Monitor Series

TCP – Delivered Energy Test



WARNING!

▲ Table of Contents ▲ Section Contents

Shock hazard. Avoid contact with the energy meter. Dangerous voltages will be present on energy meter electrode plates/posts.

To verify the defibrillator delivered energy:

 Connect the UUT to the defibrillator analyzer. Make sure the QUIK-COMBO (+) terminal is connected to apex (+).

Note: Adapt this procedure to use standard paddles, if desired.

- 2. Set the defibrillator analyzer to measure energy, with the appropriate scale.
- 3. Turn on the UUT. Verify that the ADVISORY indicator is off. If not, refer to **Entering Manual Mode**.
- 4. Press the ENERGY SELECT control to select 2 J.
- 5. Press the CHARGE control and wait for the UUT to reach full charge. Press the SHOCK control to discharge the UUT energy.

Note: Verify that the defibrillator analyzer shows an energy level between 1.0 and 3.0 J.Not all energy levels listed in the Delivered Energy Test table (below) are available on every UUT.

Back

Index

Next Page

3201896_R_PIP-TCP.pdf Page 64 of 69

TCP – Delivered Energy Test

6. Repeat Steps 4 through 6 for the remaining available energy levels specified in the Delivered Energy Test table below.

Energy Level (J)	Acceptable Output (J)	Energy Level (J)	Acceptable Output (J)
2	1.0 to 3.0	70	66.5 to 73.5
10	9.0 to 11.0	100	97.5 to 102.5
15	14.0 to 16.0	360	351.0 to 369.0
50	47.5 to 52.5	-	

Back

(Continued on next page)

Next Page

Index

3201896_R_PIP-TCP.pdf Page 65 of 69

▲ Table of Contents ▲ Section Contents

Previous Page

LIFEPAK 20 Defibrillator/Monitor Series

TCP – Defibrillator Output Waveform Test (Optional)



The Defibrillator Output Waveform Test is an optional test.

- 1. Connect the UUT to a defibrillator analyzer using the QUIK-COMBO electrode cable. Set the defibrillator analyzer to ENERGY, 1000 J scale.
- 2. Connect the DEFIB and GND terminals on the defibrillator analyzer to an oscilloscope vertical channel input and ground input. Set the oscilloscope to 0.5 V/div, 2 ms/div, + slope, store mode, and single sweep.

Note: 1 V on the oscilloscope = 29 A defibrillator output current using the QED-6 energy meter. When using other energy meters, refer to the manufacturer's specifications. You may need to slow down the horizontal sweep and/or turn on the triggering high-frequency reject to successfully capture the waveform.

- 3. Turn on the UUT. Press the ENERGY SELECT control and select 360 J.
- 4. Press the CHARGE control. After the capacitor charges (the SHOCK indicator is blinking), press the SHOCK control to deliver the energy to the analyzer.
- 5. Verify that the waveform meets specifications.
- 6. When testing is complete, turn off the UUT and disconnect the test setup.

(Continued on next page)

3201896_R_PIP-TCP.pdf Page 66 of 69

▲ Table of Contents ▲ Section Contents

Back



TCP – Defibrillator Output Waveform Test (Optional)



1. Delivered waveform at 360 J into given resistive load.

2. Discharge polarity is APEX positive, STERNUM negative for Phase 1.

Index

Next Page

3. Tilt =
$$\frac{+I_1 - |I_4|}{I_1}$$
,

3201896_R_PIP-TCP.pdf Page 67 of 69

Back

LIFEPAK 20 Defibrillator/Monitor Series

TCP – Therapy Defibrillation Isolation Test

TCP- Therapy-Defibrillation Isolation Setup



3201896_R_PIP-TCP.pdf Page 68 of 69



▲ Table of Contents ▲ Section Contents



Index

Next Page 🕨

TCP – Therapy Defibrillation Isolation Test

TCP- Therapy-Defibrillation Isolation

To test for therapy defibrillation isolation after a therapy repair:

WARNING!

Shock hazard. Electrical energy is discharged during this procedure. Do not allow the paddle electrodes to contact any person or conductive surfaces except as described below.

- 1. Establish the setup shown in the figure on the previous page.
- 2. Verify the defibrillator analyzer is on and the display displays ENERGY. If not, turn on the defibrillator analyzer and press the ENRG softkey.
- 3. Turn on the UUT.
- 4. Press the ENERGY SELECT control and select 360 J.
- 5. Press the CHARGE control. After the capacitor charges (the SHOCK indicator is blinking), press the SHOCK control to deliver the energy to the analyzer.
- 6. Verify the defibrillator analyzer indicates a delivered energy of less than 2J.
- 7. Turn off the device.

3201896_R_PIP-TCP.pdf Page 69 of 69

ents



Index